## Standardised Architectural Modules for Layouts

**Checklist: Power supply and other requirements for the CSSD equipment** (for 4 operating rooms)

The list given below is only indicative; please make changes to (a) size/capacity of the equiment listed here; (b) include additional equipment required; c) power supply requirements;

| S No | Equipment | Dimensions | Size / Footprint | Amperage | | | Supply | | | Water Connection | Others (please mention) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | L x W | | Watts | 5A | 15A | General | Stabilised | Uninterrupted | | |
| **A** | **Linen washing room** | | | | | | | | | | |
| 1 | Textile Processing Machine (Washing Machine) | 1.2 x 0.9 | 25 Gauge | 3HP | | | Y | | | Y | Drainage |
| 2 | Hydro Extractor | 1.2 x 0.8 | 25 Gauge | 3HP | | | Y | | | Y | Drainage |
| 3 | Tumble Drier | 1.4 x 0.9 | 25 Gauge | 5 HP | | | Y | | | | Exhaust pipe |
| **B** | **Linen packing area** | | | | | | | | | | |
| 1 | Folding Area | 2.6 x 0.6 | | | | | Y | | | | |
| **C** | **Gas sterilisation area** | | | | | | | | | | |
| 1 | Ethylene Oxide Sterilizer | 1.05 x 0.7 | 5 CFT | 0.5 HP | | | Y | | | | Exhaust pipe to the terrace |
| 2 | Ethylene Oxide Sterilizer | 0.65 x 0.5 | 2 CFT | 0.25HP | | | Y | | | | |
| **D** | **Sterilization room** | | | | | | | | | | |
| 1 | Double door autoclave | 2.6 x 1.6 | 24 SR DD HVP | 18KW | | | Y | | | Y | Air supply pipes inlet for fresh air & outlet |